

KANSAS  
STATE CORPORATION COMMISSION

*R*

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 122-20 County: Barber

Location: SW NE NW Sec. 3 Twp. 34 Rge. 11 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4529

I have this date completed supervision of plugging of:

Lease Name: Finnup "D" Well No. 1

Operator's Full Name: Petroleum Inc.

Complete Address: R.R. Great Bend, Kans.

Plugging Contractor: Morgan Casing Pulling Co.

Address: Hutchinson, Kans. License No. \_\_\_\_\_

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1 PM Day 12 Month September Year 1958

The above well was plugged as follows:

230' of 8 5/8" surface casing circulated with cement. 10 sack cement placed on bottom from 4490' to 4460'. Top perf. 4490'. Pipe was shot and pulled to 1800' where it was circulated with 50 sack jell mud. Pipe pulled. Hole filled to 270' with heavy mud. Rock bridge set from 270' with 20 sack cement placed top plug. Heavy mud to 35' with rock bridge set and 10 sack cement to base of cellar.

Signed: *W. L. ...*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1958

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 3 T. 34 R. 11W  
BOOK PAGE 122 LINE 20