

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clarke Corporation

Complete Address Box 187 Medicine Lodge, KS

Lease Name Bevans Well No. 1

Location SE/SE/SE Sec. 6 Twp. 34 Rge. 11 (E) (W) W

County Barber Total Depth 4733

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corporation

Address Box 187 Medicine Lodge, KS License No. 583

Operation Completed: Hour 1:00 PM Day 28 Month 3 Year 1974

The above well was plugged as follows:
285 ft 8 5/8 surface cemented with 225 sacks. 4728 ft 5 1/2 long string
cemented with 125 sacks. Top perf. 4576 ft. Sand to 4550 ft, 5
sacks cement with bailer. Pulled 2800 ft 5 1/2. Set 10 ft rock bridge
at 200 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/2/74
INV. NO. 8838-W