

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Casey of Cities Service has this

date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1228, Guymon, Oklahoma

Lease Name: Fletcher "C" Well No. 1

Location: NW NW SE Sec. 27 Twp. 33 Rge. 43 (E) (W)

County: Morton Total Depth 3425' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 600' circulated w/ cement. 5 1/2" to 3424' cemented.

Top perforations 2926' Plug bottom w/ 20 sacks cement.

Top of cement 2727' Mud 2727' to 600'

Spot 40 sacks cement 600' to 440' Mud 440' to 30'

Plug, Hulls & 10 sacks cement. 30' to 0'.

Weld Plate on 8 5/8" casing.

Very truly yours,

Edward Eves
Conservation Division Agent