

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Casey of Cities Service Oil Co. has this  
date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1028, Guymon, Oklahoma

Lease Name: Fletcher "D" Well No. 1

Location: APEC N/2 Sec. 34 Twp. 33 Rge. 43 (W)

County Morton Total Depth 3180' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 600' circulated w/ cement. 5 1/2" to 3174' cemented.

Top Perforations 2908' Plug bottom w/ 25 sacks cement.

Top of cement 2793' Mud 2793' to 650'

Spotted 35 sacks cement 650' to 550' Mud 550' to 35'

Plug, Hulls & 10 sacks Cement 35' to 10' Pump.

STATE CORPORATION COMMISSION

Very truly yours,

JUN 23 1966

CONSERVATION DIVISION  
Wichita, Kansas  
Edward J. Lives  
Conservation Division Agent