



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAY 15 1973

CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service has this date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: 3545 NW 58th Street, Oklahoma City, Oklahoma

Lease Name: Hoffman "E" Well No. 2

Location: C SE NW Sec. 12 Twp. 32 Rge. 34 ~~(E)~~ (W)


County: Seward Total Depth 5900' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Troy was instructed to plug the well as follows:

8 5/8" to 1664' circulated w/ cement.	Mud 5900' to 5571'
Spot 55 sacks cement 5571' to 5421'	Mud 5421' to 4220'
Spot 35 sacks cement 4220' to 4120'	Mud 4120' to 2630'
Spot 70 sacks cement 2630' to 2430'	Mud 2430' to 1664'
Spot 15 sacks cement 1664' to 1619'	Mud 1619' to 1060'
Spot 45 sacks cement 1060' to 925'	Mud 925' to 45'
Plug, Halls & 15 sacks cement 45' to 0'.	

Very truly yours,

  
Conservation Division Agent