

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Casey of Coral Oil & GAS has this

date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Coral Gas & Oil Inc.

Complete Address: 409 Bank of Southwest Bldg., Amarillo, Texas

Lease Name: U.S. Government Well No. 1

Location: C SE NW Sec. 25 Twp. 32 Rge. 34 (E) (W)

County: Seward Total Depth 5900' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Casey was instructed to plug the well as follows:

13 3/8" to 468' circulated w/ cement. 4 1/2" to 5935' cemented.

Top perforations 5693' Plug bottom w/ 20 sacks cement.

Top of cement 5509' Mud 5509' to 460'

Spot 80 sacks cement 460' to 360' Mud 360' to 30'

Plug, Hulls & 20 sacks cement 30' to 0'.

Very truly yours,

Conservation Division Agent