

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1973

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Patrick has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Patrick Petroleum Corporation

Complete Address: 300 Insurance Bldg., Wichita, Kansas

Lease Name: Hitch Well No. 1

Location: NW NW SE Sec. 31 Twp. 32 Rge. 34 ~~(E)~~ (W)

County: Seward Total Depth 6425' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1708' circulated w/ cement. 5 1/2" to 6240' cemented.

Top perforations 6140' Plug bottom w/ 25 sacks cement.

Top of cement 5950' Mud 5950' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent