

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1972

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Patrick of Patrick has this

date requested permission to plug the following described well:

Mr. Patrick guarantees payment of the plugging fee.

Operator's full Name: Patrick Well Service

Complete Address: 852 Petroleum Road, Liberal, Kansas

Lease Name: E.C. Dean Well No. 1-2

Location: 1250' FSL & 1250' FEL Sec. 2 Twp. 32 Rge. 42 (E) (W)

County: Morton Total Depth 5370' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Patrick was instructed to plug the well as follows:

7 5/8" to 1458' circulated w/ cement. 4 1/2" to 5369' cemented.

Top perforations 5051' Plug bottom w/ 15 sacks cement.

Top of cement 4800' Mud 4800' to 900'

Spot 30 sacks cement 900 to 800' Mud 800' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edward J. Eise  
Conservation Division Agent