

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 8 1967

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed March 1, 1967.

Dear Sir:

Mr. Rod Sweetman of S & S Drilling Company has this
 date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Company, Inc.

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name: McKenna Well No. # 1

Location: C SW SW Sec. 3 Twp. 29 Rge. 9 (E)(W) W

County Kingman Total Depth 3010' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

238' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill
hole with drilling mud to 220', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 20 sacks. Fill hole with drilling mud to 35',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving
 Conservation Division Agent