

*U*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Texaco, Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name M. E. Plush Well No. # 1

Location C NW NW Sec. 26 Twp. 29 Rge. 8 (E) (W)W

County Kingman Total Depth 4597'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine, Lodge, Kansas License No. 583

Operation Completed: Hour 11:45AM Day 8th Month Dec. Year 1966

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cemented with 200 sacks. 2760' of 4 1/2" long  
string, cemented with 125 sacks. Plug back T.D. 2725'. Top perferation  
2687'. Bottom of the hole was sanded to 2675, and cemented with 3 sacks,  
through the dump bailer. 2253' of 4 1/2" long string was recovered from the  
hole. Fluid level in the hole was at 255'., bridge plug and rock bridge  
from 255' to 245', and cemented with 25 sacks. Hole was filled with mud  
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 12/9/66  
INV. NO. 4429-u