

15-095-20484-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 08 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - - (of this well)

Operator's Full Name Vincent Oil Corp

Complete Address 901 Union Center Bldg Wichita, KS

Lease Name Wells Well No. 1

Location C SW/NE/SW Sec. 26 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4280

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 1:00 PM Day 6 Month 10 Year 1976

The above well was plugged as follows:

246 ft 8 5/8 surface cement circulated. 4279 ft 5 1/2 long string
cemented with 100 sacks. Top perf. 4185 ft. Sand to 4100 ft, 5 sacks
cement with bailer. Pulled 3405 ft 5 1/2. Set 10 ft rock bridge at
420 ft. Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Russell B. Henderson
Well Plugging Supervisor

INVOICED

DATE 10-8-76

INV. NO. 3964-W