

KANSAS

JL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Zenith Drlg. Corp. Inc.

Complete Address Suite 600 200 W. Douglas Wichita, Ks 67202

Lease Name Calkin Well No. 1-24

Location C SW/NE Sec. 24 Twp. 29S Rge. 8 (E) (W) W

County Kingman Total Depth 4565

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Oilfield Service

Address 107 W. Fowler Medicine Lodge, Ks License No. 583

Operation Completed: Hour 9:30 AM Day 26 Month 4 Year 1971

The above well was plugged as follows:

250 ft of 8 5/8 surface pipe cemented with 225 sacks. 4200 ft of 4 1/2
long string cemented with 125 sacks. Perf. 4142-52 ft. Pumped plug
to 4050 ft with 10 sacks cement. Pulled 3300 ft of 4 1/2. Set 10 ft
rock bridge at 250 ft. Fill hole with 4 yds of redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell Biberstein*
Well Plugging Supervisor

INVOICED

DATE 4/29/71

INV. NO. 3610-U