

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1975
5-14-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Vincent Oil Corp

Complete Address 901 Union Center, Wichita, KS

Lease Name Calkin Well No. 1

Location C S/2 N/2 SE Sec. 24 Twp. 29 Rge. 8 (E) (W)

County Kingman Total Depth 4165

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Gressel Oil Field Contractor

Address Box 322 Haysville, KS License No.

Operation Completed: Hour 4:00 PM Day 12 Month 5 Year 1975

The above well was plugged as follows:

268 ft 8 5/8 surface cement circulated. 4147 ft 4 1/2 long string
cemented with 125 sacks. Open hole. Sand to 4100 ft, 4 sacks cement
with bailer. Pulled 1800 ft 4 1/2. Set 10 ft rock bridge at 240 ft,
20 sacks cement. Mud to 40 ft, plug, 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5/14/75

INV. NO. 1327-W