



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 28, 1968.

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name Handkins Well No. # 1

Location C NE SE Sec. 13 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4550'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Ks. 67202 License No.

Operation Completed: Hour 3:00PM Day 9th Month March Year 1968

The Above well was plugged as follows:

235' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole was filled with drilling mud to 225', 1st cementing plug, bridged with 1/2 sack of Gel-Mud and 1/2 sack of hulls on fluid at 225', and cemented with 35 sacks, through the drill pipe, with cement from 215' to 110'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of Gel-Mud and 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks, with cement from 30' to the base of the cellar. Rat and mouse holes bridged and cemented with 5 sacks. This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/11/68

INV. NO. 7389-W

Signed: Arlene Elving
Well Plugging Supervisor