

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed February 7, 1968.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name McNeil Well No. # 1

Location C NE SE Sec. 9 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4533'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita Ks. 67202 License No. _____

Operation Completed: Hour 3:30PM Day 17th Month February Year 1968

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole was
filled with drilling mud to 210', 1st cementing plug, bridged with 1/2 sack
of Gel-Mud and 1/2 sack of hulls on fluid at 210', and cemented with 40 sacks,
with cement from 200' to 80'. Hole was filled with drilling mud to 40',
2nd cementing plug, bridged with 1/2 sack of Gel-Mud and 1/2 sack of hulls on
fluid at 40', and cemented with 10 sacks, with cement from 30' to the base
of the cellar. Rat and mouse holes bridged and cemented with 5 sacks.
This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 2/19/68
INV. NO. 7279-W