

K
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name N.C.R.A.

Complete Address Box 6 Great Bend, KS

Lease Name Ziegler Well No. 1

Location NW/NW Sec. 8 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4550

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 10:00 AM Day 24 Month 3 Year 1975

The above well was plugged as follows:

272 ft 8 5/8 surface cemented with 250 sacks. 4549 ft 5 1/2 long string
cemented with 175 sacks. D.V. tool set at 2349 ft, 175 sacks. Bridge
plug set at 2240 ft. Perforated at 1790-95.ft. Sand to 1750 ft, 5
sacks cement with bailer. Pulled 1610 ft 5 1/2. Set 10 ft rock bridge
at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russell Biberstein*
Well Plugging Supervisor

DATE 3/26/75
INV. NO. 1049-w