

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 11 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Leben Drilling Inc.

Complete Address: 912 Central Bldg., Wichita, Kansas

Lease Name Sprecht Well No. # 1

Location C NE NW Sec. 5 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4565'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling Inc.

Address: 912 Central Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 2:00PM Day 7th Month Jan. Year 1965

The Above well was plugged as follows:

187' of 8 5/8" surface pipe, cement circulated. Hole was filled with  
drilling mud to 200', 1st cementing plug, bridged solid with dry cement  
and hulls on fluid at 200', and cemented with 25 sacks, bringing the  
top of the cement to 121'. Hole was filled with drilling mud to 40',  
2nd cementing plug, bridged solid with dry cement and hulls on fluid at  
40', and cemented with 10 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 1-12-65

INV. NO. 510-W