

KANSAS

[Handwritten mark]

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl Bldg. Wichita, Ks

Lease Name Goykendall Well No. 3

Location SW/SE/NE Sec. 36 Twp. 29S Rge. 7 (E) (W)

County Kingman Total Depth 4160

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 4:00 PM Day 11 Month 1 Year 1971

The above well was plugged as follows:

237 ft of 8 5/8 surface pipe cemented with 180 sacks. 4160 ft of
4 1/2 long string cemented with 100 sacks. Top perf. 4076 ft. Sand
back to 4050 ft, 4 sacks cement with bailer. Pulled 3300 lbs of 4 1/2.
Set 10 ft rock bridge at 225 ft. Fill hole with 4 yds of redimix
to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 1-12-71

INV. NO. 3184-w