

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl Bldg. Wichita, Ks

Lease Name Goykendall Well No. 2

Location SW/SE/NW Sec. 36 Twp. 29s Rge. 7 (E) (W) W

County Kingman Total Depth 4190

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 4:00 PM Day 7 Month 1 Year 1971

The above well was plugged as follows:

210 ft of 8 5/8 surface pipe cemented with 165 sacks. 4 1/2 long string
parted at 856 ft. 2 1/2 inch tubing set at 4152 ft. with 25 sacks
cement. Top perf. at 4110 ft, Displaced 20 sacks cement to 3900 ft.
Pulled 3200 ft of 2 1/2. Shoved plug to 200 ft, 10 ft rock bridge and
fill hole with 4 yds of redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: G. Russell Biberstein
Well Plugging Supervisor

DATE 1-12-71

INV. NO. 3183-W