

Form CP-3  
Rev. 6-26-62

*14*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 15 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Continental Oil Company

Complete Address: Box 267, Great Bend, Kansas

Lease Name Viola Shepherd Well No. # 1

Location C NE SW Sec. 3 Twp. 29 Rge. 8 (E) (W)W

County Kingman Total Depth 4712

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 12:30PM Day 10th Month June Year 1964

The Above well was plugged as follows:

268' of 10 3/4" surface pipe, cemented with 200 sacks. 4220' of 5 1/2" long  
string, cemented with 100 sacks. Plug back to 4193'. Top perferation  
4150'. Plug pushed to 4000', sand and cemented with 15 sacks. Hole was  
filled with mud to 275', with 10' of rock bridge, and cemented with 30  
sacks. Hole was filled with mud to 40', with 10' of rock bridge, and  
cemented with 15 sacks to base of the cellar.  
3330' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/15/64

INV. NO. 9309-W

Signed: Archie Elving  
Well Plugging Supervisor