

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: Box 562, Great Bend, Kansas

Lease Name Rohlman Well No. # 1

Location SW NW SW Sec. 12 Twp. 29 Rge. 9 (E) (W)W

County Kingman Total Depth 4585

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:00PM Day 28th Month June Year 1964

The Above well was plugged as follows:

180' of 8 5/8" surface pipe, cemented with 150 sacks. 4585' of 5 1/2" long
string, cemented with 150 sacks. Top perferation 4530'. Bottom of the
hole was sanded to 4520', and cemented with 5 sacks. Fluid in the hole
was bailed down to 200'. Plug was set at 200', with 10' of rock bridge,
and cemented with 25 sacks. Hole was filled with mud to 40', with 10'
of rock bridge, and cemented with 10 sacks to base of the cellar.
3400' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/29/64
INV. NO. 9380-W

Signed: Archie Elving
Well Plugging Supervisor