

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Holland Well No. # 1

Location C NE SW Sec. 28 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4585'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Ks. License No. _____

Operation Completed: Hour 4:30 AM Day 12th Month May Year 1965

The Above well was plugged as follows:

218' of 8 5/8" surface pipe, cement circulated with 165 sacks. Hole
was filled with drilling mud to 215', 1st cementing plug, bridged
solid with hulls on fluid at 215', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/13/65

INV. NO. 1154-W