

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN -1 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Shore Well No. # 1

Location C NE SW Sec. 26 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4584'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: H-30 Drilling, Inc.

Address: 200 North Main St., Wichita, Kansas License No. _____

Operation Completed: Hour 6:00AM Day 29th Month May Year 1966

The Above well was plugged as follows:

260' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 250', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 250', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/1/66

INV. NO. 3320-W

Signed: Ardie Elving
Well Plugging Supervisor