

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill;
filed October 6, 1967.

Operator's Full Name Beacon Resources Corporation

Complete Address: 412 Union Center Bldg., Wichita, Kansas 67202

Lease Name Shore Well No. # 1

Location NW SE NW Sec. 25 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4590'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: S & S Drilling Company

Address: Box 645, Great Bend, Kansas 67530 License No.

Operation Completed: Hour 2:15 PM Day 20th Month October Year 1967

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole was
filled with drilling mud to 260', 1st cementing plug, bridged with 2 sacks
of dry cement and 1/2 sack of hulls on fluid at 260', and cemented with 23
sacks, with cement from 250' to 175'. Hole was filled with drilling mud
to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack
of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30'
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Charles Elving
Well Plugging Supervisor

DATE 10/23/67

INV. NO. 6550-u