

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Cragun Well No. 1

Location C NE NW Sec. 22 Twp. 30 S Rge. 6 (E) (W) X

County Kingman Total Depth 4620

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 2 Pm Day 5 Month 12 Year 1979

The above well was plugged as follows:

262' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 2030' w/125
sax cement. Plug back to 2003' - Preforated at 1941' to 44' - Sand back to
1900' - Top sand w/4 sax mixed cement w/ dump bailer. Pull approximately
1550' 4 1/2" casing. Howco mixed & pumped 5 sax hulls - 25 sax 50/50 pos.,
cement w/ 4% gel - Mix & pump 20 sax gel & 100 sax 50/50 posmix cement
w/4% gel to top of casing. Shut in w/550# pressure.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1979

12-10-79

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 12-11-79
INV. NO. 1064-w

Signed:
Well Plugging Supervisor