

KANSAS

J.P.

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 5, 1967.

Operator's Full Name Clinton Oil Company

Complete Address: 6810 W. Highway 54, Wichita, Kansas 67209

Lease Name Reida Well No. # 3-X

Location C N/2 SW SE Sec. 19 Twp. 30 Rge. 6 (E) (W) W

County Kingman Total Depth 4241'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1:30PM Day 25th Month Sept. Year 1967

The Above well was plugged as follows:

266' of 8 5/8" surface pipe, cemented with 200 sacks. 4240' of 5 1/2" long
string, cemented with 100 sacks. This is an open hole. Bottom of the hole
was sanded to 4225', and cemented with 5 sacks, through the dump bailer,
with cement from 4225' to 4185'. 3657' of 5 1/2" long string was recovered
from the hole. Fluid level in the hole was at 260', bridge plug and rock
bridge from 260' to 250', and cemented with 25 sacks, with cement from
250' to 175'. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks, with cement from 30' to the base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 9/29/67
INV. NO. 6404-W