

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 11 1965  
6-11-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: R. R. # 2, Great Bend, Kansas

Lease Name Stevens Well No. # 1

Location NE NE SW Sec. 19 Twp. 30 Rge. 6 (E) (W)

County Kingman Total Depth 4730'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 4:40PM Day 10th Month June Year 1965

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 175 sacks. 4315' of 5 1/2" long  
string, cemented with 125 sacks. Plug back to 4248'. Top perferation  
3748'. Plug was pushed to 3725', and 50' of sand, and cemented with 5  
sacks. 2280' of 5 1/2" long string was recovered from the hole. Fluid in  
the hole was bailed to 250', bridge plug set on fluid at 250', and 10'  
of rock bridge, and cemented with 25 sacks. Hole was filled with mud  
to 40', and 10' of rock bridge, and cemented with 10 sacks to the base  
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 6/11/65  
REV. NO. 1295-W

Signed: Archie Elving  
Well Plugging Supervisor