

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-129-20632-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Cities Service Co.

Complete Address 3545 N.W. 58th St. Oklahoma City, Oklahoma 73112

Lease Name Collingwood Well No. C-4

Location 810' FNL - 660' FEL Sec. 13 Twp. 33 Rge. 43 (East) (West)

County Morton Total Depth 4750'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wabefield Drilling Co. Inc.

Address 300 W. Douglas Suite 500 Wichita Kans 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 8:30 AM Day: 5 Month: June Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

1st plug at 4600' with 50 sbx of cement. 2nd plug at 3620' with 35 sbx of cement. 3rd plug at 1400' with 50 sbx of cement. 4th plug at 680' with 25 sbx of cement. 5th plug at 40' to 0' on solid bridge with 10 sbx of cement. Then they circulated 10 sbx of cement in rat hole. The cement was pumped through drill pipe. The plugging was accomplished by ~~Wabefield~~ Dawell Cementing Co.

Amount of Surface Casing: 1354' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthis  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Out of my area & had a well in my area to beat.

Signed: Paul A. Luthis  
Conservation Division Agent

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

DATE 6-14-82 JUN - 8 1982  
INV. NO. 412 W CONSERVATION DIVISION  
Wichita Kansas