

15-095-00976-0000



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Drillers Production Co Inc

Complete Address 480 4th Natl Bldg Wichita, KS

Lease Name Bett Well No. 2

Location SW/SW/NE Sec. 26 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4185

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 11:00 AM Day 17 Month 1 Year 1974

The above well was plugged as follows:

282 ft 8 5/8 surface cement circulated. 4122 ft 5 1/2 long string
cemented with 100 sacks. Top perf. 4104 ft. Sand to 4050 ft, 5 sacks
cement with bailer. Pulled 3500 ft 5 1/2. Set 10 ft rock bridge at
200 ft, 25 sacks cement. Mud to 40 ft, 10 ft rock bridge, 10 sacks
cement to surface.

I hereby certify that the above well was plugged as herein stated

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1/22/74

INV. NO. 8428-W