

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed December 7, 1967.

Operator's Full Name Aylward Drilling Company

Complete Address: 909 First National Bank Bldg., Wichita, Kansas 67202

Lease Name Albright Well No. # 1

Location C SE NW Sec. 36 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4245'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas 67202 License No.

Operation Completed: Hour 4:00PM Day 17th Month December Year 1967

The Above well was plugged as follows:

233' of 8 5/8" surface pipe, cement circulated with 185 sacks. Hole was filled
with drilling mud to 225', 1st cementing plug, bridged with 2 sacks of dry cement
and 1/2 sack of hulls on fluid at 225', and cemented with 23 sacks, with cement
from 215' to 140'. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cem-
ented with 9 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Annie Elving
Well Plugging Supervisor

INVOICED

DATE 12/18/67
INV. NO. 6925-W