

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

WELL PLUGGING APPLICATION FORM  
(File One Copy)

RCD 10-27-86

API NUMBER N/A (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.) OCT 27 1986 6/87

LEASE OPERATOR Pickrell Drilling Company, Inc. OPERATORS LICENSE NO. 5123

ADDRESS 110 North Market, Suite 205, Wichita, Kansas 67202 PHONE # (316) 262-8427

LEASE (FARM) Rader 'A' WELL NO. 1 WELL LOCATION SW SW COUNTY Kiowa

SEC. 15 TWP. 27S RGE. 19W  (S) or  (W) TOTAL DEPTH 4790' PLUG BACK TD 4790'

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 258' CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 4785' CEMENTED WITH 200 SACKS

PERFORATED AT Produced from open hole 4785'-4790'.

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Down 4 1/2" csg pump 2 sx Hulls, 25 sx cement, 4 1/2" plug; Displace with wtr to 4470' unless hit pressure first (theoretical displacement is w/70.5 bbls to 4433'; Cut & recover pipe. Tie into 8 5/8" surface & pump 3 sx Hulls, 15 sx Gel, 70 sx cement, 10 sx gel, 1 sx Hulls, 8 5/8" plug, 110 sx cement, 8 5/8" plug, 40 sx cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 18, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Danny Biggs PHONE # (316) 793-5742

ADDRESS 2601 Canturbury Lane, Great Bend, Kansas 67530

PLUGGING CONTRACTOR Rockhold Engineering, Inc. LICENSE NO. 5111 6/87

ADDRESS Box 698, Great Bend, Kansas 67530 PHONE # (316) 792-2506

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack Gurley  
(Operator or Agent)

DATE October 24, 1986  
Jack Gurley - Engineer

①



JOHN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. McCONNELL  
BRIAN J. MOLINE

*Governor*  
*Chairman*  
*Commissioner*  
*Commissioner*  
*Executive Secretary*  
*General Counsel*

*State Corporation Commission*

**CONSERVATION DIVISION**

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

JAN 27 '87

EXPIRES

October 27, 1986

WELL PLUGGING NOTICE

Rader "A" #1  
SW SW  
Sec. 15-27S-19W  
Kiowa County

Pickrell Drilling Company, Inc.  
115 North Market, Ste. 205  
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging  
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760  
five days prior to plugging the well (KAR-82-3-113).