

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

15-095-20330-000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-09520330-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR MTM Petroleum, Inc. (owner/company name) KCC LICENSE # 6236
ADDRESS P.O. Box 82 CITY Spivey (operator's)

STATE Kansas ZIP CODE 67142 CONTACT PHONE # (316) 532-5178

LEASE Albritten WELL# 1 SEC. 17 T. 28 R. 9 (East/West)

C - SW- SE - SPOT LOCATION/QQQQ COUNTY Kingman

660 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 270 CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4463 CEMENTED WITH ? SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4369-4374

ELEVATION 1671 T.D. 4465 PBTD _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 4320' w/ 5 sks, shoot pipe, pull pipe to 1400' spot

30 sks cement, pull pipe to 900' spot 30 sks cement, pull pipe to 320' circulate cement

to surface, pull pipe - top off cement. 60/40 4% gel

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? N/A Available IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Marvin A. Miller PHONE# (316) 532-5178

ADDRESS P.O. Box 82 city/state Spivey, KS 67142

PLUGGING CONTRACTOR Shawnee Well Service, Inc. KCC LICENSE# _____

ADDRESS Attica, KS 67009 (company name) PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-15-93 AUTHORIZED OPERATOR/AGENT: Kim Adelhardt
(signature)

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1993

CONSERVATION DIVISION
(contractors)

2)

15-095-203300000



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

September 16, 1993

MTM Petroleum Inc
P O Box 82
Spivey KS 67142

Albritten #1
API 15-095-20,330
660 FSL 1980 FEL
Sec. 17-28S-09W
Kingman County

Dear Marvin A. Miller,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #2 202 W First Suite 304
Wichita KS 67202
(316) 263-8809