

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

15095-301030001
FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Completed 12-3-66 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR K & E Drilling, Inc. OPERATOR'S LICENSE NO. 5266

ADDRESS 100 S. Main, Suite 300; Wichita, KS 67202 PHONE # (316) 264-4301

LEASE (FARM) Garlich "A" WELL NO. 2 WELL LOCATION NW NW COUNTY Kingman

SEC. 24 TWP. 28S RGE. 8 ~~(E)~~ or (W) TOTAL DEPTH 4755' PLUG BACK TD 4692'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. D-13,160

SURFACE CASING SIZE 8-5/8" SET AT 252' CEMENTED WITH 175 SACKS

CASING SIZE 5-1/2" SET AT 4560' CEMENTED WITH 135 SACKS

3-1/2" set at 4561' cemented with 375 sxs Lite + 50 sxs Common

PERFORATED AT Open hole 4561'-4692'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug with 60/40 Pozmix cement w/4% gel and hulls for lost circulation control. Fill open hole and 3-1/2" to surface. Displace 252 sxs down 8-5/8"x 5-1/2" annulus.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not explain.) Not required at time of completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Al Hammersmith PHONE # (316) 792-2729

ADDRESS P.O. Box 2050, Great Bend, KS 67530

PLUGGING CONTRACTOR Allied Cementing Co. LICENSE NO. Unknown

ADDRESS P.O. Box 628, Great Bend, KS 67530 PHONE # (316) 793-5861

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Wayne L. Brinegar Vice President
(Operator or Agent)

DATE: September 11, 1990



15095-30103-0001

Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARD, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

September 12, 1990

K & E Drilling, Inc.
100 S. Main, Suite 300
Wichita, KS 67202

Garlisch "A" #2
NW NW 24-28-08W
Kingman County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #2, 202 W. First, #304
Wichita, KS 67202
(316) 263 - 8809