



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission
CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION

JUL 2 1959
 7-2-59
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director.
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date June 5, 1959, authorized the following plugging operation:

Operator's Full Name: Lee Phillips Oil Co.

Complete Address: 1407 Union Natl. Bank Bldg., Wichita, Kansas

Lease Name: Breford Well No. 1

Location: SE-SW-SE Sec. 25 Twp. 16 Rge. 11 (E) (W) X

County: Barton Total Depth: 3382


Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 280' with heavy mud--
push plug and 1/4 sack hulls to 280' and cement with 25 sacks thru
drill pipe. Fill hole to 40'--set solid bridge--cap with 10 sacks.
Fill, bridge, and cement rathole with 2 sacks.

Very truly yours,

Signed: 
 Conservation Division Agent