

15-009-05562-0000
R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 127-30

LOCATION Sec. 27E

SEC. 31 TWP. 16 RGE. 11-W

Dry Hole Abandoned Oil well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Valenta

Operator Bennett & Roberts Oil Operations Address Russell-Kans.

Field _____ County Barton

Total Depth 3083 Feet.

Plugging Contractor Miller Casing Pulling Co

Plugging Contractor's License No. 12

Address 44 Bend-Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 360 ft. Circulated with cement
5 1/2 casing set at 3091 ft. Cemented 100 sacks of cement.
Plugged back to 3000 ft with sand & chert. Dumped
5 sacks of cement at 3000 ft. Shot off & hulled the
5 1/2 casing - mud to 300 ft. Set rock bridge &
20 sacks of cement at 300 ft. mud to 35 ft.
Plug & 10 sacks of cement at the surface.

RECEIVED
STATE CORPORATION COMMISSION

C. A. Stough
District Conservation Agent

SEP 15 1953

09-15-53

Date 9-10-53

PLUGGING
FILE SEC 31 T 16 R 11W
BOOK PAGE 127 LINE 30

CONSERVATION DIVISION
Wichita, Kan.