

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -009-21901-0000 (of this well)

Operator's Full Name Miles petroleum & John R. Evans

Complete Address 405 Fourth St., Claflin, Kansas 67525

Lease Name Zorn Well No. 2

Location NW NE SW Sec. 31 Twp. 16 Rge. 11 (E) (W)

County Barton Total Depth 3328'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 3:30 Day 19 Month 9 Year 1980
PM

The Above well was plugged as follows:

Sanded back to 2950' and 5 sx cement with dump Bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

25 sx mud-gel, 1 sx hulls, and 100 sx cement.

Max. pres 500#. Shut in pres. 300#.

Recovered 2420' of 5 1/2" casing.

Plugged back to 3020'. Top perforation at 2996'.

3321' of 5 1/2" casing cemented with 175 sx cement.

252' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

Signed: Duane [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1980
CONSERVATION DIVISION
Wichita, Kansas

9-22-80

INVOICED

DATE 9-23-80

INV. NO. 3191-w