



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Fred I. Murfin of Murfin Drilling Co. has this

date requested permission to plug the following described well:

Mr. Fred I. Murdin guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company

Complete Address: 617 Union Center, Wichita, Kansas

Lease Name: Frees Well No. # # 3

Location: NE SE NW Sec. 34 Twp. 16 Rge. 11 (E) (W)

County Barton Total Depth 3384 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Russell Hoberecht was instructed to plug the well as follows:

8 5/8" 301' Cwc.

Sanded hole back to 3365' & dumped 4 sax cement with

dump bailer. Mudded hole to 300'; set rock bridge; dumped

8 sax cement on bridge. Let set over-nite, bailed hole

dry & displaced 17 sax cement. Mud to 40'; set rock bridge;

displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Trause  
Conservation Division Agent