

15-009-15134-0000

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 7 1967

CONSERVATION DIVISION  
Wichita, Kansas

3-7-67

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. M. C. Sheek of Hinkle Oil Company has this  
date requested permission to plug the following described well:

Mr. J. B. Hinkle guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Company

Complete Address: 1016 Union Center, Wichita, Kansas

Lease Name: Kroutwurst Well No. # 8

Location: SW SE SW Sec. 34 Twp. 16 Rge. 11 (E)(W) W

County Barton Total Depth 3337 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Dwight Dellinger was instructed to plug the well as follows:

8 5/8" 102' Cwc.

Sanded hole back to 3300' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 20' sax mud & 100 sax cement with mud

pump, cementing from 230' to base of cellar.

Very truly yours,

Don L. Lusk  
Conservation Division Agent