



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Damme of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. James J. Simmons guarantees payment of the plugging fee.

Operator's full Name: National Oil Company
200 W. Douglas, Suite 550,
Complete Address: Wichita, Kansas 67202

Lease Name: Homolka Well No. # 1

Location: SE NE NE Sec. 35 Twp. 16 Rge. 11 (E)(W) W

County: Barton Total Depth 3390 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fred Damme was instructed to plug the well as follows:

8 5/8" csg. 237' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 50 sax
cement thru drill pipe. Mud to 230' & displaced 25 sax cement thru
drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax
cement with Halliburton Cementing Company's pump truck, cementing to
base of cellar.

Very truly yours,

Don L. ...
Conservation Division Agent