

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 37-30

LOCATION CNE-SE

SEC. 11 TWP. 22 RGE. 12-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Feed Voigt

Operator Buche-Preis Oil Corp Address Box #268 - Tulsa - Okla

Field \_\_\_\_\_ County Stafford

Total Depth 3677 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 633 ft. Circulated with cement  
5/8 casing set at 3640 ft. Cemented with 110 sacks cement  
Plugged back to 3470 ft with chat. Dumped 5 sacks of  
cement at 3470 ft. Shot off & pulled 1/2" casing  
Filled with mud to 250 ft. Set Rock Bridge & 15 sacks of  
cement at 250 ft. Mud to 30 ft. Bridge & 10 sacks of  
cement at the surface.

Murray Pipe Pulling Co. Plugging Contractors

RECEIVED  
STATE CORPORATION COMMISSION

NOV 8 - 1950 11-8-50

CONSERVATION DIVISION

Wichita *Carly Stouck*

District Conservation Agent

**PLUGGING**  
FILE NO. 37-30  
PAGE 37 LINE 3

Date 11-6-50