

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 141-20

LOCATION NW SW NE

SEC. 12 TWP. 22 RGE. 12

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Willinger

Operator Birmingham-Bartlett Address 300 Kaufman Bldg Wichita

Field _____ County Stafford

Total Depth 3637 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 196' circulated with cement - 6 1/2" at 3628' with 100
sax cement behind.

Filled with sand to 3620' set 5 sax cement with dump bailer,
pulled 3200' 5 1/2", filled with mud to 196' set rock bridge and
15 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

2-26-52

PLUGGING
FILE SEC 141-20
PAGE 141-20-245

FEB 26 1952

J. P. Kelly
District Conservation Agent

Wichita, Kansas
Date

2-22-52