

KANSAS

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

*Rec'd
6-1-66*

Operator's Full Name Petroleum Management, Inc.

Complete Address: Box 922, Great Bend, Kansas

Lease Name Willinger Well No. # 1

Location NE NW SE Sec. 12 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3572'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 2:15 PM Day 29th Month June Year 1966

The Above well was plugged as follows:

208' of 8 5/8" surface pipe, cemented with 175 sacks. 3569' of 5 1/2" long
string, cemented with 125 sacks. Top perforation 3254'. Bottom of the
hole was sanded to 3225', and cemented with 5 sacks, through the dump
bailer. 2725' of 5 1/2" long string was recovered from the hole. Bridge
plug was pushed in fluid to 204', rock bridge from 204' to 196'. 65
sacks of cement was pumped through 180' of 2" tubing, cementing the
hole from 196' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/1/66
INV. NO. 3489-U