

16
KANSAS
STATE CORPORATION COMMISSION

15.185.12913.0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Voight Well No. # 4

Location NE NW SW Sec. 12 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3614'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950 El Dorado, Kansas License No. 547

Operation Completed: Hour 3:30 PM Day 16th Month Nov. Year 1965

The Above well was plugged as follows:

195' of 8 5/8" surface pipe, cemented with 200 sacks. 3610' of 5 1/2" long
string, cemented with 150 sacks. This is an open hole. Bottom of the hole
was sanded to 3600', and cemented with 5 sacks. 2500' of 5 1/2" long string
was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed
in fluid to 195', rock bridge from 195' to 185'. 2 sacks of Cal-Seal was
mixed in a barrel, and put on plug at 185', through the dump bailer, and let
set for 2 hours. Hole was bailed dry, and 25 sacks of cement was added to the
plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cem-
ented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/17/65
INV. NO. 2197-W