

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

11-15-65
NOV 15 1965

Operator's Full Name H. C. Bennett CONSERVATION DIVISION
Wichita, Kansas

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Voight Well No. # 3

Location NW NE SW Sec. 12 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3611'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 11:45AM Day 12th Month Nov. Year 1965

The Above well was plugged as follows:

233' of 8 5/8" surface pipe, cemented with 200 sacks. 3605' of 5 1/2" long string, cemented with 110 sacks. This is an open hole. Bottom of the hole was sanded to 3600', and cemented with 5 sacks. 2660' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 230', rock bridge from 230' to 220', 4 sacks of cement was mixed in a barrel, and put on plug at 220', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 21 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/15/65
INV. NO. 2178-W