

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-185-00431-0000

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Voight Well No. # 2

Location NE NW SW Ne Ne Sw Sec. 12 Twp. 22 Rge. 12 (E) (W)W

County Stafford Total Depth 3665'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 11:45AM Day 30th Month Oct. Year 1965

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cemented with 200 sacks. 3665' of 5 1/2" long  
string, cemented with 125 sacks. Top perferation 3616'. Bottom of the  
hole was sanded to 3600', and cemented with 5 sacks. 2700' of 5 1/2" long  
string was recovered from the hole. Fluid was up in the hole. Bridge  
plug was pushed in fluid to 210', rock bridge from 200' to 190', 4 sacks  
of cement was mixed in barrel, and put on plug at 190', through the dump  
bailer, and let set over-night. Next morning hole was bailed dry, and 21  
sacks of cement was added to the plug. Hole was filled with mud to 40',  
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11/1/65

INV. NO. 2078-4