

KANSAS
STATE CORPORATION COMMISSION

15.185-13100-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

NOV 8 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Voight Well No. # 6

Location SE NE SW Sec. 12 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3618'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 9:00 AM Day 6th Month Nov. Year 1965

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 200 sacks. 3610' of 5 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole
was sanded to 3600', and cemented with 5 sacks. 3000' of 5 1/2" long string
was recovered from the hole. Fluid was up in the hole. Bridge plug was
pushed in fluid to 265', rock bridge from 265' to 255', 4 sacks of cement
was mixed in barrel, and put on plug at 255', through the dump bailer,
and let set over-night. Next morning hole was bailed dry, and 21 sacks of
cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 11/9/65

INV. NO. 2149-W