


KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

NOV 5 1965

CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name H. C. Bennett
 Complete Address: 1212 Union National Bldg., Wichita, Kansas
 Lease Name Voight Well No. # 5
 Location NE SE SW . Sec. 12 Twp. 22 Rge. 12 (E) (W)N
 County Stafford Total Depth 3613'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Flint Engineering & Construction Company
 Address: Box 950 El Dorado, Kansas License No. 547
 Operation Completed: Hour 9:45 AM Day 4th Month Nov. Year 1965

The Above well was plugged as follows:

168' of 8 5/8" surface pipe, cement circulated. 3609' of 5 1/2" long string,
cemented with 75 sacks. This is an open hole. Bottom of the hole was sanded
to 3600', and cemented with 5 sacks. 2880' of 5 1/2" long string was recovered
from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to
165', rock bridge from 165 to 155', 4 sacks of cement was mixed in barrel,
and out on plug at 155', through the dump bailer, and let set over-night.
Next morning hole was bailed dry, and 21 sacks of cement was added to the
plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
 Well Plugging Supervisor

DATE 11/5/65
 INV. NO. 2114-W