

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. 144-30
 LOCATION SE-7E-SW
 SEC. 6 TWP 22 RGE 12

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Krankenburg
 Operator Stanolind Oil & Gas Co. Address Box 7, Ellenwood, Ks.
 Field _____ County Stafford
 Total Depth 3660 Feet.
 Plugging Contractor West Supply Co. Inc.
 Plugging Contractor's License No. 14
 Address Chase, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 251' o.w.c. 4 1/2" Oil string
set 3655' w/ 150 sv cem. Sand to 3645" dump
3 sv cem. Shot off and pulled 4 1/2" casing.
Filled hole with heavy mud to 240'
set rock bridge and dumped 20 sv cem.
mud to 35' rock bridge and 10 sv cem.
to base of collar.

Warren H. Horner
 District Conservation Agent

Date Sept 29, 1955

PLUGGING

FILE SEC 6 T 22 R 12 W
 BOOK PAGE 144 LINE 30

RECEIVED
 STATE CORPORATION COMMISSION

OCT 3 1955

10-3-55

CONSERVATION DIVISION
 Wichita, Kansas