

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1964
9-10-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name H. Krankenberg Well No. # 2

Location C SW SW Sec. 6 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3666

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company

Address: 1450 Maple, Russell, Kansas License No. 9

Operation Completed: Hour 12:15 PM Day 9th Month Sept. Year 1964

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cemented with 175 sacks. 3658' of 5 1/2" long string, cemented with 100 sacks. Bottom of the hole was sanded to 3640', and cemented with 5 sacks. Fluid level was up in the hole. Bridge plug was pushed to 260', and 10' of rock bridge. 4 sacks of cement was mixed in a barrel, and put on plug through dump bailer, and let set over-night. Next morning hole was bailed down, and filled to the base of the cellar with ready-mix cement.

2684' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/10/64

INV. NO. 9989-W

Signed: Archie Elving

Well Plugging Supervisor