

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasSEP 10 1964
9-10-64
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Pan American Petroleum CorporationComplete Address: P. O. Box 432, Liberal, KansasLease Name H. Krankenberg Well No. # 4Location C NW SW Sec. 6 Twp. 22 Rge. 12 (E) (W) WCounty Stafford Total Depth 3663Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Barnes & Sons Pipe Pulling CompanyAddress: 1450 Maple, Russell, Kansas License No. 9Operation Completed: Hour 11:45AM Day 9th Month Sept. Year 1964

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated. 3660' of 5 1/2" long string,
cemented with 100 sacks. Bottom of the hole was sanded to 3650', and cem-
ented with 5 sacks. Fluid level was up in the hole. Bridge plug was push-
ed in fluid to 240', and 10' of rock bridge. 4 sacks of cement was mixed
in a barrel, and put on plug through dump bailer, and let set over-night.
Next morning hole was bailed down, and filled to the base of the cellar
with ready-mix cement.

1000' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

9/10/64

INV. NO.

9490-W

Signed:

Archie Elving
Well Plugging Supervisor